

Silver Fox Grid Station P.U.D.
Preliminary Estimated Water and Wastewater Flows

Description	Units	# /Size	Rate gpd/unit	Daily Flow gpd
Data Center Buildings				
per employee / visitor 2 shifts 4 Bldgs	Employees	264	15	3960
Loading Bays (Data Center Bldgs)				
2 Loading Bays Per Bldg	Loading Bay	8	100	800
Sec., AI Lab, C.T.E. Bldg & Guard House				
per employee / visitor 2 shifts	Employees	48	15	720
Total				5,480

15 gallons per day (GPD) per employee
 100 GPD per loading bay

Flow Source: Florida Administrative Code 64E-6 Sewage Flows

Employee estimates based on Google Data Centers staffing levels:
 Reference: Google Data Center, The Dalles, Oregon (1.3M SF, ~200 employees all shifts)